

February 20, 2009

**ADDENDUM NO. 2
FOR THE CONSTRUCTION OF THE
WATSON PARK REMEDIATION AND PH I IMPROVEMENTS**

Notice is hereby given that the following revisions, additions, and/or deletions are hereby made a part of and incorporated into the plans and specifications for the Watson Park Remediation and Phase I Improvements Project.

PROJECT PLANS

1. Sheet C-DM-6: Demolition, Top Soil and Vegetation Disposal Areas.

DELETE Legend description note and **REPLACE** with "Area that can be filled with demolition debris, AC, Concrete crushed to <1', topsoil, existing stockpile soil, and other excavated contaminated material including that shown on C-GP-4, at approval of City to elevation above existing grade specified."

DELETE Note No. 1 and **REPLACE** with "Contractor is responsible to verify that any debris, AC/Concrete crushed to <1', topsoil, or contaminated soil materials placed within the hatched areas shown on this drawing are capped with a minimum of 3' of clean soil and are placed and compacted per project specifications."

DELETE Note No. 2 and **REPLACE** with "NO construction debris, chipped vegetation, contaminated soil, and/or top soil shall be placed within 5' from footprint of proposed edge of structure, skate park, or sport court."

DELETE Note No. 3 and **REPLACE** with "City's approval of the type of debris materials or contaminated soil, as well as area and method of disposal required prior to placement of any debris, vegetation, contaminated soil, or top soil within these designated areas shall be required."

2. Sheet G-GP-4: Additional Excavation Plan

DELETE note "Total excavation=20000 CY and **REPLACE** with "Total excavation=25000± CY"

3. Sheet L-DT-2: Construction Details

REPLACE Detail A/L-DT- 2 name with "DG paving or groundcover area redwood headerboard detail"

4. Sheet L-PP-1: Planting Plan

DELETE Planting Plan Note No. 13.

5. Sheet L-PD-1: Planting Details

DELETE all erosion control blanket callout notes on planting details and **REPLACE** with "Erosion control blanket at slopes 2:1 and greater. Erosion control blanket shall be Geojute blanket or approved equal."

6. Sheet E-6: Soccer Field Lighting and Details

CHANGE all "60'-0" High Pole" notes in Fixture Schedule table **TO** "70'-0" High Pole."

PROJECT SPECIFICATIONS

1. Attachment 6-California Integrated Waste Management Board-Grant Agreement

DELETE "April 30, 2009" in Section 1.02 Grant Term and **REPLACE** with "October 31, 2010."

DELETE "December 31, 2007" in Section 1.03 Deadlines and **REPLACE** with "May 31, 2009."

DELETE "April 30, 2009" in Section 1.03 and **REPLACE** with "October 31, 2010."

2. Section 01205 Health and Safety

CLARIFICATION HASP have provisions to eliminate the requirement for lead monitoring and 40-Hr HAZWOPER training following grading of the Site, provided that remaining construction activities do not include additional excavation below the 3' cap. Work following grading such as but not limited to utility trench construction or foundation construction, that penetrates the cap, must be performed according to the entire provisions of the HASP for a contaminated site. Additionally, provisions within the HASP related to general construction activities must be in place during the entire project.

3. Section 02200 Earthwork

DELETE Section 1.2.E and **REPLACE** with "No off-haul is permitted as part of this project. Excess clean or contaminated material will be disposed of on site as shown on sheet C-DM -6 and as directed by the CITY.

4. Section 02900 Planting


DELETE Section 2.02.L.

INSTRUCTIONS

The bidder must sign this addendum in the space provided below and return one signed copy with the bid.

Failure to return the signed copy with bid documents shall not relieve the bidder of the obligation to include this addendum to the bid proposal.

APPROVED BY:


KATHERINE JENSEN
Division Manager
City Facilities Architectural Services Division
Department of Public Works

Bidder's Name _____

Signature and Title of Bidder _____

Date _____