

**Schedule of Quantities
for the
Huff Avenue at S. Baywood Avenue Sidewalk Improvement Project**

Item	Spec. Section	Description	Unit	Quantity	Unit Price	Extension
1	5-2	Street Clean-up (\$450 Min. per day) (Revocable)	DAY	5		
2	15-3	Additional Potholing for Existing Utilities (Revocable)	EA	2		
3	15-5	Adjust Water Valve Casing to Grade (Revocable)	EA	1		
4	15-6	Adjust Water Meter Box to Grade (Revocable)	EA	1		
5	15-7	Remove and Re-install Signs	EA	3		
6	15-8	Remove and Relocate Mail Box	EA	1		
7	15-9	Utility Conflict Work	FA	1		
8	19-2	Roadway Excavation	CY	33		
9	21-1	Class A Subgrade Preparation	SF	950		
10	39-1	10" AC Deep Lift	TON	61		
11	39-1	2" AC Surface	TON	24		
12	39-3	Conform Cut (2' wide, 0.17' deep)	LF	475		
13	39-4	Sawcut	LF	505		
14	73-2	PCC Curb & Gutter Type - A2 (Including Base)	LF	260		
15	73-2	PCC Sidewalk (Including Base)	SF	2,100		
16	73-2	PCC Driveway and Driveway Conforms (Include Base)	SF	225		
17	73-3	Install PCC Wheelchair Ramp with Detectable Warning Surface (Include Base)	EA	4		