

April 13, 2009

**ADDENDUM NO. 2
FOR THE
HAPPY HOLLOW PARK AND ZOO PEDESTRIAN BRIDGE REBID PROJECT**

Notice is hereby given that the following revisions, additions and/or deletions are hereby made of, and incorporated into plans and specifications for the **HAPPY HOLLOW PARK AND ZOO PEDESTRIAN BRIDGE REBID PROJECT**.

SPECIFICATIONS – CONTRACT DOCUMENTS

1. SPECIAL PROVISIONS: LIQUIDATED DAMAGES: (near end of Special Provision)
The dollar amount for each day the completion is delayed by the contractor shall be changed to \$7,500

SPECIFICATIONS AND PLANS (Clarifications)


2. PLAN SA2 and SECTION 02741, Asphalt Concrete: The bid includes some asphalt, base rock quantities for access roads per notes on Sheet SA1 and SA2. This is a means and methods requirement and it depends on the size and weight of equipment needed to complete the job. The quantities are included as a worst case probability and bidder's quantities may vary.
3. PLANS SA 1 and SA 2: Attention is directed to Note No. 7 on SA 1 and Note Nos. 1, 4 & 5 on SA2 concerning the access paths.
4. SECTION 02920 & 02950: Attention is directed towards Addendum No. 1 for soil and sodding requirements.
5. GENERAL: N.I.C. is an abbreviation for Not In Contract. All work labeled as such is not in the contract.
6. PLAN D1, "Demolition and Tree Protection": The quantity of work associated with limbing of trees is difficult to indicate on plans compared to the dollar amount of work involved. Please note that the plan attempts to identify the trees requiring branches to be removed and that additional trees may need to be limbed if they have branches in the way of the new bridge. Please note that access into the Riparian Corridor is limited to foot traffic only for the purposes of limbing certain trees.

7. SECTION: 05120, Part 1.1.D.3. Attention is directed to this section. "All other miscellaneous metal furnished that is shown on the contract plans, except those included in Section 05520 Bridge Railing and Fencing."
8. SECTION 05520, Part 2.1.A: Bridge fencing steel shall be ASTM A709, Grade 50, galvanized per Sheet S48 Note 2 and S49 Note 2. Bridge gate steel shapes and plates shall conform to ASMT A709, Grade 50 Galvanized.
9. SECTION 09910, Part 1.1.A: Delete "...including the bridge posts at the observation deck and supports for the bridge gates," from Specification Section 09910 1.1.A.
10. SECTION 09910 Part 2.1.D: Color; "...shall be brown to match the weathering steel of the structural steel."
11. PLANS S17, S21, S22: Paint steel as indicated on drawings, i.e. shown on Sheets S17, S21, S22 (knuckle joint, Grade 50W) per SECTION)9910, Part 2.1.D above.
12. SECTION 03301, Part 2.1.E.1: Add to Specification Section 03301 2.1.E.1 "Deck and abutment **and exposed piles:** Class 1 Finish"
13. PLANS S48: Add the note to attach plastic lumber railing to C-channel, "Use #10x1 1/4" deep thread wood screws at 12" O.C. or approved equal."
14. The pavement and base section are part of the Happy Hollow Park and Zoo Project.
15. PLAN S11: Pier Foundation Details; Attention is directed to ADDENDUM NO. 1 for the grade elevations at center pier.
16. PLANS S16 & S17: Knuckle joints are not hot dip galvanized. See S16 Note 3. All steel except the internal steel plates shall conform to ASTM A709, Grade 50W, unless otherwise noted, and painted."

INSTRUCTIONS TO BIDDER:

The bidder must sign this addendum in the space provided below and return one signed copy with the bid. Failure to return the signed copy with the bid documents shall not relieve the bidder of the obligation to include this addendum with the bid proposal.

APPROVED BY:


for Katy Allen
Director
Public Works Department

Bidder's Name

Date

Signature & Title of Bidder