CITY OF
SAN JOSE
CAPITAL OF SILICON VALLEY

Department of Transportation
HANS F. LARSEN - ACTING DIRECTOR

March 2, 2010

ADDENDUM No. 2
For the
2010 PROP 1B STREET RESURFACING PROJECT

Notice is hereby given that the following revisions, additions and/or deletions are hereby made to, and incorporated into the Plans and Specifications for the above project.

CHANGES IN PROJECT PLANS & SPECIFICATIONS:

1- On 2010 PROP 1B STREET RESURFACING PROJECT Specifications, TECHNICAL SPECIFICATIONS, section 39-1, page 64, third paragraph shall say:

Asphalt concrete surface course (overlay) shall be placed in a compacted thickness of 2" (inches) as shown in the estimated quantity table.

2- On 2010 PROP 1B STREET RESURFACING PROJECT Specifications, ESTIMATED QUANTITY TABLE, Pages 138 and 139

Replace pages 138 and 139 with the attached Estimated Quantity Table.

INSTRUCTIONS:

The **bidder must sign this addendum** in the space provided below and **return one signed copy with the bid.** Failure to return the signed copy with the bid document shall not relieve the bidder of the obligations to include this addendum to the bid proposal.

APPROVED BY:

RENE CORDERO
Division Manager

Bidder's Name

Signature and Title of Bidder

Date

ESTIMATED QUANTITY TABLE

ZONE	STREET NAME	FROM	TO	TOTAL PAVEMENT AREA (SQ FT)	AC (TONNAGE) 2" OVERLAY	REMOVE AND REPLACE (SQ YARDS)	SAMIR – R (SY)	SLURRY SEAL (SY)	CURB & GUTTER (LF)M	COLD PLANE 0.10' DEEP	PAVING MAT INTERLAYERAVING MAT INTERLAYER (SY)	MONUMENTS	WATER VALVES	MANHOLES (STANDARD)	GUTTER CUT (LF)	CONFORM CUT (SQ FT)
118	LAKEWOOD DR	CROPLEY	SIERRAWOOD DR	98,181	1331	1,304	0	0	96	0	9,221	9	9	24	6,387	810
209	BYERLEY AV	LINCOLN AV	GLEN UNA WY	21,850	222	1,015	0	0	193	0	1,884	0	2	4	1,998	558
311	BANGOR AV	ORCHARD PARK DR	HERMA ST	17,280	241	531	0	0	13	0	1,638	1	0	2	1,137	810
311	BANGOR AV	HERMA ST	TONOPAH DR	23,296	325	579	0	0	0	0	2,208	5	1	11	1,532	810
311	CHRIS DR	COPCO LN	ROHN WY	23,360	321	289	0	0	53	0	2,214	2	1	5	1,536	407
311	COLVILLE DR	BANGOR AV	ZILEMAN DR	39,840	542	621	0	0	11	0	3,777	5	5	9	2,618	407
311	COPCO LN	LEAN AV	CALPINE DR	46,592	630	854	0	0	36	0	4,417	3	1	8	3,061	814
311	GRANDIN CT	COLVILLE DR	E END	6,880	95	182	0	0	0	0	652	1	0	1	455	0
311	ROHN WY (northside)	CHRIS DR	350 ' W/O CHRIS DR	23,360	321	56	0	0	96	0	2,214	3	0	3	1,662	407
405	GABLE LN	MARY JO WY	HARLOW WY	16,960	232	149	0	0	32	0	1,608	0	1	1	1,116	407
405	HARLOW WY	GABLE LN	BLOSSOM HILL RD	35,520	485	1,267	0	0	0	0	3,367	0	2	2	2,334	407
411	FAIRDELL DR	ANDALUISA WY	HUSTED AV	15,516	218	543	0	0	0	0	1,471	2	0	1	1,022	810
414	CARDIN AV	WILLOWMONT AV	SHAW DR	22,401	22	572	2,613	2,613	96	3,000	0	1	1	1	0	0
414	CHURCH DR	ELECTRA AV	MARKS AV	16,380	18	530	1,911	1,911	0	2,457	0	0	0	1	0	0
414	CORNING DR	SHAW DR	CHAMBERS DR	13,761	14	515	1,605	1,605	42	1,806	0	1	0	2	0	0
414	CORNING DR	CHAMBERS DR	WILLOWMONT AV	7,524	7	275	878	878	86	987	0	0	0	0	0	0
414	ELECTRA AV	BRYAN AV	KIMBERLY DR	35,199	26	761	4,107	4,107	18	3,423	0	2	0	8	0	0
414	ESTELLE AV	THOMPSON AV	CARDIN AV	17,118	17	533	1,997	1,997	190	2,247	0	0	0	2	0	0
414	FAIRHAVEN CT	FAIRHAVEN DR	S END	4,401	4	20	513	513	60	504	0	1	0	1	0	0
414	FAIRHAVEN DR	INVICTA DR	OVERBROOK DR	25,281	25	475	2,949	2,949	100	3,318	0	1	0	6	0	0
414	HAUCK DR	ZISCH DR	INVICTA WY	37,764	37	782	4,406	4,406	0	4,956	0	0	0	2	0	0
414	HUGO LN	QUINLAN LN	ELECTRA AV	11,421	11	267	1,332	1,332	46	1,428	0	1	0	11	0	0

ZONE	STREET NAME	FROM	TO	TOTAL PAVEMENT AREA (SQ FT)	AC (TONNAGE) 2" OVERLAY	REMOVE AND REPLACE (SQ YARDS)	SAMIR – R (SY)	SLURRY SEAL (SY)	CURB & GUTTER (LF)M	COLD PLANE 0.10' DEEP	PAVING MAT INTERLAYERAVING MAT INTERLAYER (SY)	MONUMENTS	WATER VALVES	MANHOLES (STANDARD)	GUTTER CUT (LF)	CONFORM CUT (SQ FT)
414	KIMBERLY CT	ELECTRA AV	W END	12,960	11	249	1,512	1,512	16	1,449	0	1	0	1	0	0
414	LUPINE CT	FAIRHAVEN DR	S END	4,194	4	220	489	489	5	483	0	1	0	1	0	0
414	MARKS AV	BRYAN AV	WILLOWMONT AVE	34,362	34	581	4,009	4,009	61	4,599	0	3	1	5	0	0
414	MYRTLE AV	OVERBROOK DR	INVICTA WY	26,272	26	633	3,065	3,065	53	3,448	0	0	0	2	0	0
414	OVERBROOK DR	MYRTLE AV	HILLSDALE AV	19,197	19	384	2,240	2,240	0	2,520	0	0	0	1	0	0
414	QUARTZ WY	MARKS AV	ELECTRA AV	18,396	18	167	2,146	2,146	24	2,415	0	0	0	1	0	0
414	THOMPSON AV	SHAW DR	ESTELLE AV	14,238	14	393	1,661	1,661	65	1,920	0	0	0	0	0	0
414	WILLOWDALE DR	WILLOWPARK DR	MERIDIAN AV	37,440	37	945	4,368	4,368	170	4,914	0	0	0	1	0	0
414	WILLOWDALE DR	WILLOWVIEW DR	BLOSSOMVIEW DR	27,684	27	8	3,230	3,230	130	3,633	0	0	0	0	0	0
414	WILLOWGATE DR	WILLOWPARK DR	MERIDIAN AV	37,440	37	663	4,368	4,368	95	4,914	0	1	0	1	0	0
414	WILLOWMONT AV	ELECTRA AV	ZISCH DR	25,920	26	633	3,024	3,024	24	3,442	0	2	0	3	0	0
414	WILLOWOOD DR	WILLOWMONT AV	JACOB AV	32,904	32	203	3,839	3,839	119	4,200	0	0	0	1	0	0
414	WILLOWPARK DR	WILLOWMONT AV	JACOB AV	32,004	32	486	3,734	3,734	126	4,200	0	2	0	5	0	0
414	WILLOWVIEW DR	JACOB AV	WILLOWMONT AV	32,004	32	932	3,756	3,756	125	4,200	0	3	0	3	0	0
414	ZISCH DR	WILLOWMONT AV	MYRTLE AV	14,976	15	322	1,747	1,747	34	2,037	0	0	0	3	0	0
415	BRYAN AV	ALMADEN EX	CHERRY AV	87,300	1100	1,444	0	0	230	0	8,400	4	1	17	5,043	911
420	PRINCE ROYAL PL	BRANHAM LN	N END	8,559	117	510	0	0	0	0	683	1	1	2	476	407
420	ROYAL FOREST CT	BRANHAM LN	N END	10,953	148	359	0	0	16	0	910	2	1	2	633	407
420	ROYAL GROVE CT	BRANHAM LN	N END	12,717	172	533	0	0	14	0	1,077	2	1	2	749	407
422	CAS DR	LOS ARBOLES	EZIE ST	11,200	156	554	0	0	0	0	1,062	0	3	5	1,515	810
499	BRANHAM LN EAST	150 S/O BATTLE DANCE DR	GREY GHOST	15,936	219	555	0	0	0	0	1,511	0	0	2	1,049	407
499	BRANHAM LN EAST	BATTLE DANCE DR	150 S/O BATTLE DANCE DR	9,300	127	10	0	0	0	0	455	1	4	3	318	2,133
519	ACAPULCO DR	FENIAN DR	WREN WY	104,202	1410	2,233	0	0	650	0	9,707	13	1	23	6,723	3,633
519	KINGSTON WY	MANITOBA DR	WESTMONT AV	74,277	989	2,446	0	0	280	0	6,883	8	0	9	4,768	810
519	RINCON AV	CITY LIMIT	SAN TOMAS AQUIN	108,423	1456	1,427	0	0	600	0	10,243	6	4	24	7,071	2,023